First Description of an RND-Type Multidrug Efflux Pump in *Achromobacter xylosoxidans*, AxyABM[∇]

Julien Bador, Lucie Amoureux, Jean-Marie Duez, Anthony Drabowicz, Eliane Siebor, Catherine Llanes, and Catherine Neuwirth

Department of Bacteriology, University Hospital of Dijon, BP 37013, 21070 Dijon Cedex, France, ¹ and Department of Bacteriology, University of Franche-Comte, Faculty of Medicine, F-25030 Besançon, France²

Received 14 March 2011/Returned for modification 16 May 2011/Accepted 22 July 2011

Achromobacter xylosoxidans is an emerging pathogen in cystic fibrosis patients. The multidrug resistance of these bacteria remains poorly understood. We have characterized in a clinical strain the first resistance-nodulation-cell division (RND)-type multidrug efflux pump in this species: AxyABM. The inactivation of the transporter component axyB gene led to decreased MICs of cephalosporins (except cefepime), aztreonam, nalidixic acid, fluoroquinolones, and chloramphenicol.

Achromobacter xylosoxidans is a nonfermentative Gram-negative bacillus considered to be an opportunistic agent (1, 25). It is an emerging pathogen in cystic fibrosis (CF) (6, 20). Currently, 120 patients are followed at our CF center, of whom 24 (20%) have been colonized at least once by A. xylosoxidans. It has recently been suggested that A. xylosoxidans might be responsible for a high inflammatory response and therefore might be involved in the decline in lung function (9). This microorganism exhibits innate antibiotic multiresistance, including resistance to cephalosporins (except ceftazidime), aztreonam, and aminoglycosides (1, 2, 8, 22). There are only a few reports that describe resistance mechanisms in this species. To date, only the constitutive oxacillinase OXA-114 (7) and a couple of acquired β-lactamases belonging to VEB, IMP, and VIM families have been described (11, 15, 21, 23, 24). Nevertheless the mechanisms of intrinsic resistance of A. xylosoxidans to cephalosporins, aztreonam, and aminoglycosides remain unknown.

Resistance-nodulation-cell division (RND)-type efflux pumps are widely present among nonfermentative Gram-negative bacilli (3–5, 10, 14, 17, 19). In a preliminary experiment on *A. xylosoxidans*, we investigated the effect of reserpine, an efflux pump inhibitor, on MIC values of various antibiotics commonly used to treat CF patients. We observed an increased activity of drugs from different families such as β -lactams, fluoroquinolones, and tetracyclines. This prompted us to investigate the presence of an efflux mechanism in this species.

For this purpose, we chose the clinical strain AXX-A, isolated in our laboratory. This strain harbors a wild-type antibiotic resistance phenotype (Table 1): it is susceptible to ticarcillin, ceftazidime, carbapenems, and ciprofloxacin but resistant to cephalothin, cefoxitin, cefotaxime, cefepime, aztreonam, nalidixic acid, and aminoglycosides. The strain was identified by using the API20NE system (bioMérieux, Marcy l'Etoile, France) and confirmed by 16S rRNA gene sequencing.

We designed multiple sets of primers in conserved regions of RND efflux genes from *Pseudomonas aeruginosa*, *Stenotro-phomonas maltophilia*, and *Burkholderia cenocepacia*. With the primers MexB2-F and MexB2-R (Table 2) we amplified in AXX-A a 1,097-bp sequence sharing 88% similarity with the *acrB* gene from *Bordetella bronchiseptica*. We then determined the complete sequence of a putative RND efflux operon by using the two-step gene walking method (16). This operon is composed of three putative open reading frames (ORFs) encoding a membrane fusion protein (designated AxyA), a RND transporter protein (AxyB), and an outer membrane protein (AxyM). Upstream and in an inverted orientation we detected an ORF encoding a transcriptional regulator belonging to the LysR family (AxyR) without any homology with MexR.

The standard protein BLAST program (http://blast.ncbi.nlm .nih.gov/Blast.cgi) was used to detect protein sequence similarities. The gene products AxyA, AxyB, and AxyM showed very strong homologies with putative RND-type efflux proteins from *A. xylosoxidans* A8, *Achromobacter piechaudii* ATCC 43553, and *Bordetella bronchiseptica* RB50 (Fig. 1). The putative efflux systems have not been studied in these species. Nevertheless, AxyB shares 72% identity with the *P. aeruginosa* MexB protein, which is the RND transporter component of the well-characterized MexAB-OprM efflux system (18). We sequenced the *axyABM* operon in both AXX-A and another clinical strain (AXX-C) entirely. While AXX-A and AXX-C AxyABMs share 99% similarity, the percentage of identity was surprisingly lower (90 to 94%) for AxyABM from the environmental strain *A. xylosoxidans* A8.

We studied the role of AxyABM in the innate antibiotic resistance of A. xylosoxidans by inactivating axyB in AXX-A. The suicide plasmid pINAP1, derived from vector pUC18, was constructed in $Escherichia\ coli\ DH5\alpha\ cells$ by cloning a 977-bp EcoRI-HindIII PCR fragment internal to the axyB gene (nucleotide positions 3847 to 4823 in axyABM) obtained with primers INA-axyB-2F and INA-axyB-2R. Then pINAP1 was introduced into AXX-A by electroporation. The recombinant AXX-A (axyB::Tic), named AXX-A-DP, was selected on Mueller-Hinton agar plates containing 50 μ g/ml of ticarcillin. The axyB disruption by pINAP1 integration was confirmed by

^{*} Corresponding author. Mailing address: Laboratoire de Bactériologie, Hôpital Universitaire, Plateau technique de Biologie, BP 37013, 21070 Dijon Cedex, France. Phone: 33-3 80 29 32 60. Fax: 33-3 80 29 32 80. E-mail: catherine.neuwirth@chu-dijon.fr.

[▽] Published ahead of print on 1 August 2011.

TABLE 1. MICs of 24 antibiotics for AXX-A and AXX-A-ΔP (axyB::Tic)

Antibiotic	MIC (μg/ml) for:	
	AXX-A	AXX-A-ΔP
Ticarcillin	0.25	>256
Ticarcillin-clavulanic acid	0.5	0.5
Cephalothin	24	12
Cefuroxime	>256	>256
Cefotetan	>256	32
Cefoxitin	>256	128
Ceftriaxone	≥256	12
Cefotaxime	>256	12
Ceftazidime	4	1.5
Cefixime	>256	32
Cefepime	16	16
Aztreonam	>256	16
Imipenem	1	1
Meropenem	0.094	0.094
Nalidixic acid	24	6
Norfloxacin	8	4
Ofloxacin	2	1
Levofloxacin	0.75	0.38
Ciprofloxacin	0.75	0.5
Tobramycin	16	16
Amikacin	≥256	≥256
Tigecycline	4	4
Colistin	4	4
Chloramphenicol	12	6

PCRs (two sets of primers, AL-BAP1-F1/M14 and M14R/AL-BAP1-R1). The absence of axyB expression in AXX-A- Δ P was demonstrated by reverse transcription-PCR with primers RT-INA-R0 and RT-INA-F1 (AXX-A was used as a positive control). We determined the MICs of a panel of antibiotics for AXX-A and AXX-A-ΔP by using the Etest method (bioMérieux, Marcy l'Etoile, France). The MICs of most of the cephalosporins and aztreonam drastically decreased as a result of the axyB inactivation (by more than 20-fold for ceftriaxone and cefotaxime) (Table 1). The activity of nalidixic acid, fluoroquinolones, and chloramphenicol was also enhanced in AXX-A- ΔP . Thus, the inactivation of axyB in AXX-A led to increased susceptibility to several antibiotics belonging to different families. However, no variation was noticed for imipenem, meropenem, colistin, tigecycline, and aminoglycosides. Therefore, AxyABM is not involved in the innate resistance of A. xylosoxidans to aminoglycosides. Spontaneous revertants

TABLE 2. Primers used in the study

TABLE 2. Timers used in the study		
Primer	Nucleotide sequence (5'-3')	
MexB2-F	AACGTGCAGATTTCCTCCGG	
MexB2-R	TGTACCTGGGCGAACAGTAC	
INA-axyB-2F.	GGG <u>GAATTC</u> TCTATCGCCAGTTCTCCATCA ^a	
	GGGAAGCTTGCGCACGTACCATTTGTCCA ^b	
AL-BAP1-F1.	TGTACCTGTTCCTGCAGAAC	
M14F ^c	CCAGGGTTTTCCCAGTCACGA	
M14R ^c	GCGGATAACAATTTCACACAGGA	
AL-BAP1-R1.	AAGTACACGTCGTTGGACAG	
RT-INA-R0	ACCATGTCGCCATCCTTGTT	
RT-INA-F1	GTGTTCATCCCGATGGCGTT	

^a The EcoRI restriction site introduced into the primer is underlined.




FIG. 1. Amino acid sequence similarities (%). MFP, membrane fusion protein (AxyA and homologues); RNDt, RND transporter (AxyB and homologues); OMP, outer membrane protein (AxyM and homologues); A.x. A8, A. xylosoxidans A8; A.p., Achromobacter piechaudii ATCC 43553; B.b., Bordetella bronchiseptica RB50; P.a., Pseudomonas aeruginosa PAO1.

were obtained by cultivating AXX-A- ΔP without ticarcillin. The loss of the inserted pINAP1, confirmed by PCRs, led to phenotypic reversion.

This is the first description of an antibiotic resistance mechanism by efflux within the genus Achromobacter. Antibiotics commonly used for the management of lung infections in CF patients, like ceftazidime and ciprofloxacin, are substrates of this efflux system. AxyABM shares some properties with MexAB-OprM from P. aeruginosa since it exports β-lactams (except imipenem), fluoroguinolones, and chloramphenicol but not aminoglycosides (12, 13, 18). However, unlike MexAB-OprM, AxyABM exports neither cefepime nor meropenem. From our preliminary study, we noticed a decrease in tigecycline MIC in the presence of reserpine for the AXX-A strain. These data strongly suggest that tigecycline is a substrate for an efflux system. The MIC of tigecycline was not changed following axyB inactivation in AXX-A; tigecycline is therefore not a substrate for AxyABM. It is likely that other efflux systems take part in the antibiotic resistance of A. xylosoxidans.

^b The HindIII restriction site introduced into the primer is underlined.

^c Primer designed in pINAP1.

4914 BADOR ET AL. Antimicrob. Agents Chemother.

In conclusion, we have shown that the AxyABM efflux system is one of the mechanisms involved in the innate multidrug resistance of *A. xylosoxidans*. Furthermore, it can extrude antibiotics widely used to treat CF patients. Therefore, its role in acquired antibiotic resistance and its regulation mechanisms remain to be explored.

Nucleotide sequence accession number. The nucleotide sequence reported here has been assigned accession number JF514544 in the GenBank database.

We acknowledge the contributions of Gael Belliot and Philip Bastable for revising the manuscript.

REFERENCES

- Aisenberg, G., K. V. Rolston, and A. Safdar. 2004. Bacteremia caused by Achromobacter and Alcaligenes species in 46 patients with cancer (1989– 2003). Cancer 101:2134–2140.
- Almuzara, M., et al. 2010. In vitro susceptibility of Achromobacter spp. isolates: comparison of disk diffusion, Etest and agar dilution methods. Int. J. Antimicrob. Agents 35:68–71.
- Alonso, A., and J. L. Martinez. 2000. Cloning and characterization of SmeDEF, a novel multidrug efflux pump from Stenotrophomonas maltophilia. Antimicrob. Agents Chemother. 44:3079–3086.
- Burns, J. L., C. D. Wadsworth, J. J. Barry, and C. P. Goodall. 1996. Nucleotide sequence analysis of a gene from *Burkholderia (Pseudomonas) cepacia* encoding an outer membrane lipoprotein involved in multiple antibiotic resistance. Antimicrob. Agents Chemother. 40:307–313.
- Chan, Y. Y., T. M. Tan, Y. M. Ong, and K. L. Chua. 2004. BpeAB-OprB, a multidrug efflux pump in *Burkholderia pseudomallei*. Antimicrob. Agents Chemother. 48:1128–1135.
- De Baets, F., P. Schelstraete, S. Van Daele, F. Haerynck, and M. Vaneechoutte. 2007. Achromobacter xylosoxidans in cystic fibrosis: prevalence and clinical relevance. J. Cyst. Fibros. 6:75–78.
- Doi, Y., L. Poirel, D. L. Paterson, and P. Nordmann. 2008. Characterization
 of a naturally occurring class D beta-lactamase from *Achromobacter xylosoxi-*dans. Antimicrob. Agents Chemother. 52:1952–1956.
- Glupczynski, Y., W. Hansen, J. Freney, and E. Yourassowsky. 1988. In vitro susceptibility of *Alcaligenes denitrificans* subsp. *xylosoxidans* to 24 antimicrobial agents. Antimicrob. Agents Chemother. 32:276–278.
- Hansen, C. R., et al. 2010. Inflammation in Achromobacter xylosoxidans infected cystic fibrosis patients. J. Cyst. Fibros. 9:51–58.
- Hearn, E. M., J. J. Dennis, M. R. Gray, and J. M. Foght. 2003. Identification and characterization of the emhABC efflux system for polycyclic aromatic

- hydrocarbons in *Pseudomonas fluorescens* cLP6a. J. Bacteriol. **185**:6233–6240.
- Iyobe, S., et al. 2002. Detection of a variant metallo-beta-lactamase, IMP-10, from two unrelated strains of *Pseudomonas aeruginosa* and an *Alcaligenes xylosoxidans* strain. Antimicrob. Agents Chemother. 46:2014–2016.
- Lister, P. D., D. J. Wolter, and N. D. Hanson. 2009. Antibacterial-resistant Pseudomonas aeruginosa: clinical impact and complex regulation of chromosomally encoded resistance mechanisms. Clin. Microbiol. Rev. 22:582–610.
- Masuda, N., et al. 2000. Substrate specificities of MexAB-OprM, MexCD-OprJ, and MexXY-oprM efflux pumps in *Pseudomonas aeruginosa*. Antimicrob. Agents Chemother. 44:3322–3327.
- Moore, R. A., D. DeShazer, S. Reckseidler, A. Weissman, and D. E. Woods. 1999. Efflux-mediated aminoglycoside and macrolide resistance in *Burkholderia pseudomallei*. Antimicrob. Agents Chemother. 43:465–470.
- 15. Neuwirth, C., et al. 2006. VEB-1 in *Achromobacter xylosoxidans* from cystic fibrosis patient, France. Emerg. Infect. Dis. 12:1737–1739.
- Pilhofer, M., et al. 2007. Characterization of bacterial operons consisting of two tubulins and a kinesin-like gene by the novel two-step gene walking method. Nucleic Acids Res. 35:e135.
- Poole, K. 2001. Multidrug efflux pumps and antimicrobial resistance in *Pseudomonas aeruginosa* and related organisms. J. Mol. Microbiol. Biotechnol. 3:255-264
- Poole, K., K. Krebes, C. McNally, and S. Neshat. 1993. Multiple antibiotic resistance in *Pseudomonas aeruginosa*: evidence for involvement of an efflux operon. J. Bacteriol. 175:7363–7372.
- Poole, K., and R. Srikumar. 2001. Multidrug efflux in *Pseudomonas aeruginosa*: components, mechanisms and clinical significance. Curr. Top. Med. Chem. 1:59–71.
- Razvi, S., et al. 2009. Respiratory microbiology of patients with cystic fibrosis in the United States, 1995 to 2005. Chest 136:1554–1560.
- Riccio, M. L., L. Pallecchi, R. Fontana, and G. M. Rossolini. 2001. In70 of plasmid pAX22, a bla_{VIM-1}-containing integron carrying a new aminoglycoside phosphotransferase gene cassette. Antimicrob. Agents Chemother. 45: 1249–1253.
- Saiman, L., et al. 2001. Identification and antimicrobial susceptibility of Alcaligenes xylosoxidans isolated from patients with cystic fibrosis. J. Clin. Microbiol. 39:3942–3945.
- Shibata, N., et al. 2003. PCR typing of genetic determinants for metallobeta-lactamases and integrases carried by gram-negative bacteria isolated in Japan, with focus on the class 3 integron. J. Clin. Microbiol. 41:5407–5413.
- Sofianou, D., A. Markogiannakis, E. Metzidie, S. Pournaras, and A. Tsakris.
 2005. VIM-2 metallo-beta-lactamase in *Achromobacter xylosoxidans* in Europe. Eur. J. Clin. Microbiol. Infect. Dis. 24:854–855.
- Tena, D., A. Gonzalez-Praetorius, M. Perez-Balsalobre, O. Sancho, and J. Bisquert. 2008. Urinary tract infection due to Achromobacter xylosoxidans: report of 9 cases. Scand. J. Infect. Dis. 40:84–87.